

LOCUST FORK PARK AND STREET PAVING BID FORM

UNCLASSIFIED EXCAVATION FOR NEW BASE AND PAVING APROX 6" 16 CY

DENSE GRADED BASE FOR NEW PAVING AND PIPE BACKFILL APPROX 30TONS

REMOVEAND REPLACE EXISTING CMP WITH 18" ADS N12 20LF.

ASPHALT PAVING AT THE PARK ALDOT 424A ½" MIX 284 TON

PARK ROAD: 220LBSPER/SY424A½" MIX 270 TONS

PRICE INCLUDES MILLING A 4" TRANSITION AT THE FACE OF THE GUTTER TO CREATE A FLUSH TIE-IN. AND CLIPPING EDGE OF PAVEMENT AS NEED TO ORIGINAL EDGE OF PAVEMENT. CHEVRON STRIPES ON SPEED BUMPS TO BE INCLUDED.

PRICE INCLUDES TEMP STRIPING AND THEN PERMANET STRIPPING AFTER 14 DAYS FOR PARKING SPACES AT THE END OF PARK ROAD ON THE LEFT. TWO 14 FEET HANDICAP VANACCESSIBLE SPOTS CLOSEST TO THE WALKING TRACK, THEN TWENTY, 9 FEET WIDE HANDICAP SPACES

THE AWARD WILL BE BASED ON OUR QUANTITIES AND YOUR UNIT PRICES. PAYMENT WILL BE BASED ON ACTUAL IN PLACE QUANTITIES.

***THE TOWN OF LOCUST WILL BE RESPONSIBLE FOR PURCHASING THE ASPHALT
PLANT MIX. ALL OTHER MATERIAL NEEDED IS TO BE INCLUDED IN
CONTRACTORS BID PRICE***